KADUR DIVISION.

The 24th August 1904.

1. Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kadur Division, up to 20th September 1904, for restoring the Gadihalli tank, Registered No. 629, Tarikere Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1905.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chikmagalur between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 (Two hundred) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring the Gadihalli tank, Registered No. 629, Tarikere Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Approximate quantities of estimate for restoring Gadihalli tank, Registered No. 629, Tarikere Taluk:—

Items of work.	*Per.*	*Quantity.*
Bund—		
Earth-work to bund, watering and tamping	C. yd.	12,376
Old stone resetting with new jelly	,,	606
New stone work	,,	2,874
Gravel backing to revetment	,,	1,303
Turfing	Sq. yd.	10,000
Grade stones with painting, etc.	Each	35
Index stones	,,	35
B. M. stones	,,	2
Registered number stone	,,	1
Year stone	,,	1
Gauge stone, complete	,,	1
Breach work, as detailed in body	Lump sum.	
Clearing jungle	Lump sum.	
Sluice—		
Cutting and refilling the bund	C. yd.	179
Earth-work excavating foundation	Lump sum.	
Burnt brick in surki mortar	C. ft.	414
Burnt stone slabs	Sq. ft.	190
Plastering with surki mortar	Sqr.	5·00
Cutting lower and upper orifices together with Gibbets, cross slab.	Lump sum.	
Preparing and putting plugs for orifices, etc.	Lump sum.	
Left sluice channel—		
Opening cut a new channel for a mile's length with 3 feet bottom width and 1 : 1 side slopes in cutting, fall 2 feet per mile.	Lump sum.	
Waste weir, 220 feet long at R. L. 51·00—		
Earth-work, soft rocky soil	C. yd.	48
Burnt brick in surki mortar	C. ft.	1,409
Burnt stone slabs	Sq. ft.	961
Clearing draft, soft rocky soil	C. yd.	214
Rough stone work	,,	304
Plastering with surki mortar	Sqr.	12·17

H. J. MOLLOY, *Executive Engineer.*